

ESTIMATION FOR FINISHING CONSTRUCTION OF THE CLINIC BUILDING.

NAME OF WORK; CONSTRUCTION OF CLINIC BUILDING

ORGANISATION; SOUTH SUDAN CHILD FOUNDATION.

FOUNDER; HIS LORDSHIP ARCHBISHOP PAULINO LUKUDU LORO.

S NO.	PARTICULARS	AREA m3	RATE PER m3	AMOUNT UGX	AMOUNT EUROS	
1	Brick masonry including the cost of transportation and labor charges.					
	Long walls	2.75				
	Cross Walls	2.75				
	Another walls	17.72	1900.00	11,869,300	3,500 EUROS.	
	Deductions	2.75				
	Doors	3.86				
	windows	5.52				
2	Supply and fixing of doors and windows including transportation and labor charges.					
	Deductions					
	Doors	16.80	3200.00	13,560,000	4,000 EUROS.	
	windows	24.0				
	Plastering with C.M(1.4) 20mm thick including labor and transportation charges.					

3	Long walls	204.60				
	Cross walls	288.92				
	Another walls 1	173.72	120.0	8,453,200	2,400 EUROS.	
	Another walls 2	37.20				
4	Flooring with vertificent tile in required sizes 10 cms hick 40 mm H.B.G metal including transportation and labor charges.					
	Clinic wards	84.06				
	Office rooms	9.00	800.00	8,164,800	2,000 Euros	
	Staff rooms	9.00				
5	Provision of Electrical charges			981,300	350 Euros.	
	TOTAL				12,250 Euros.	

Prepared by site Engineer

Engineer Majok Guan.